



NOTES:

- THE VEGETATION-FREE ZONE MAY BE COMPOSED OF TYPICAL STONE BALLAST OR CONCRETE PAVERS AND WILL BE DEPENDENT ON BALLAST DESIGN REQUIREMENTS. CONTACT HYDROTECH FOR BALLAST DESIGN REVIEW.
- ADDITIONAL LAYER(S) OF INSULATION UNDER PERIMETER BALLAST, AS DEPICTED, MAY BE OMITTED PROVIDED ALTERNATIVE TRAY RETENTION IS INSTALLED.
- ROOT STOP IS LOOSE LAID OVER THE HYDROFLEX 30 AND LAPPED A MINIMUM OF 5 FEET OR 2.5 FEET WITH LAPS TAPED WITH ROOT STOP TAPE.
- REFER TO DETAILS GA-2A AND GA-2B FOR ADDITIONAL EXTENSIVE GARDEN ROOF ASSEMBLY BUILD-UP OPTIONS.



GARDEN ROOF ASSEMBLY

AMERICAN HYDROTECH, INC.

**TYPICAL GARDEN ROOF TERMINATION
PERIMETER PARAPET CONDITION
INSTAGREEN GT-4**

SCALE: NONE
DATE: 3/14/17

GA-10

This information is intended only for general conceptual purposes. It is based on data and knowledge considered to be true and correct. It is offered for the user's consideration, investigation and verification and is not intended to substitute for the advice provided by appropriate professionals. Hydrotech assumes no liability for the use of this information. The determination of the suitability and applicability of this information is the sole responsibility of the user.